


VOL, DE TERRAP, RUA RIACHUELO							
Estaca	Área de Corte (m²)	Área de Aterro (m²)	Volume de Corte (m3)	Volume de Aterro (m3)	Volum, Corte Acum, (m3)	Volum Aterro Acum, (m3)	Volume Líquido (m3)
0+035,07	0,00	0,00	0,00	0,00	0,00	0,00	0,00
0+037,00	10,40	0,00	10,05	0,00	10,05	0,00	10,05
0+039,00	7,78	0,00	18,18	0,00	28,23	0,00	28,23
0+041,00	5,96	0,00	13,74	0,00	41,97	0,00	41,97
0+043,00	4,71	0,00	10,67	0,00	52,64	0,00	52,64
0+045,00	4,07	0,00	8,78	0,00	61,42	0,00	61,42
0+047,00	4,77	0,00	8,84	0,00	70,26	0,00	70,26
0+049,00	5,84	0,00	10,61	0,00	80,87	0,00	80,87

VOLUME DE REFORÇO DE SUBLEITO RUA RIACHUELO			
ESTACA	ÁREA (m²)	VOLUME (m³)	VOLUME ACUMULADO (m³)
0+35,07	0,00	0,00	0,00
0+37,00	2,06	1,99	1,99
0+39,00	2,06	4,12	6,10
0+41,00	2,06	4,12	10,23
0+43,00	2,06	4,13	14,35
0+45,00	2,07	4,13	18,49
0+47,00	2,07	4,14	22,62
0+49,00	1,85	3,91	26,54

LEGENDA:

TERRENO NATURAL

TERRENO PROJETADO



Prefeitura de Almirante Tamandaré do Sul

OBRA: *Capejamento CBUQ* ÁREA: *14,30 x 10,00m + 0,00 (BOCAS) = 143,00m²*

01 / 01 ENDEREÇO: *RUA RIACHUELO*

11/02/20 PRANCHA: *DETALHAMENTO* ESCALA: *1 / 1*